

Office of the Municipal Executive  
Sisaiya, Kanchanpur  
Sudurpaschim Province, Nepal

सुदूरपश्चिम प्रदेश  
कान्छनपुर  
सिसैया

### Bill of Quantity

486122.11

कुल लागत

अर्थिक वर्ष : २०८३/०८३

योजनाको नाम : धरमपुर वैजनाथ मन्दिरमा मेसनीरी वाल र ट्रस्ट निर्माण  
योजना कार्यचयन हुने स्थल: बेदकोट नगरपालिका-०५

| S.n.         | Description of Items                                                                                                                                                                                                                                 | Quantity | Unit | Rate (Nrs.) |          | Amount (Nrs.) |          | Remarks |
|--------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-------------|----------|---------------|----------|---------|
|              |                                                                                                                                                                                                                                                      |          |      | In Figure   | In words | In Figure     | In words |         |
| 1            | Excavation in soft clay and silty soil having lead upto 10m & lift upto 1.5m as per Drawing and Technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer | 16.15    | cum  |             |          |               |          |         |
| 2            | Stone Soiling work in foundation trench & Levelling including 30 m lead                                                                                                                                                                              | 4.04     | cum  |             |          |               |          |         |
| 3            | P.C.C work 1.36 m Foundation Wall including 30 m lead by manual means                                                                                                                                                                                | 3.96     | cum  |             |          |               |          |         |
| 4            | Stone masonry work in cement mortar 1:6 including 10 m lead and 5 m lift as per Drawing and Technical Specifications                                                                                                                                 | 35.60    | cum  |             |          |               |          |         |
| 5            | Earth work Filling in with Ordinary soil, spreading in layers of 15/15 cm, spraying water & Manual Compaction.                                                                                                                                       | 20.70    | cum  |             |          |               |          |         |
| Total Amount |                                                                                                                                                                                                                                                      |          |      |             |          |               |          |         |
| Vat 13%      |                                                                                                                                                                                                                                                      |          |      |             |          |               |          |         |
| Grand Total  |                                                                                                                                                                                                                                                      |          |      |             |          |               |          |         |

Name Of The Contractors  
Date  
Sign  
Stamp